



Notes:

1 Electrical Contractor to provide two (2) 20A circuits with dedicated neutrals. Provide one (1) 30A twist lock connector for each circuit on a 2G plate near AV Rack location. See AV 1.5b for AV Rack location, coordinate with Telecom Contractor.

2 Electrical Contractor to provide one (1) duplex AC receptacle at all TV locations.

-Devices on plan are not shown to scale-



Owner: City of Nampa	Project: New Library AV Systems
Drawn By: E. Wheeler	Sheet Title: AV Power Plan
Sheet Number: AV-1.8b	Date: February 2014
	Revision: 5