

March 15, 2016 ADDENDUM #2 IFB 16-17 VIENNA COMMUNITY CENTER SECURITY ACCESS ******ATTENTION BIDDERS*******

(To be completed and returned with bid response)

1. EXTENSION OF BID DUE DATE: BIDS SHALL NOW BE DUE ON MARCH 24, 2016 AT 11:00:00 AM.

- 2. Q: The general contractor will be providing all the electrified locking mechanisms for doors 103 and 130, but there is no mention of electrified hardware for door 141.
 - A: Per the Contract Specifications, the General Contractor (Keller) has hardware for the electronic security doors included in his SOW. This includes Electric Hinges, Harnesses, Electric Latch Retraction Exit Devices, and Power Supplies. In the case of Door 103, the hardware also includes automatic door operator switches. Only the Card Reader is furnished and installed by the Security Contractor. Card Readers are to be provided for Doors 103 (noted in HW Set 8), Doors 130, and Door 141.
 - Door 130 does require a Card reader (not indicated in the Contract Specifications HW set 18) to be furnished and installed by the Security Contractor.
 - Door 141 does require a Card reader (not indicated in the Contract Specifications HW Set 23) to be furnished and installed by the Security Contractor. Electric hardware will have to be added to the General contractors SOW.
- 3. Q: I know the scope of work indicates we provide all the locking mechanisms, but is it correct that the Door Schedule dictates equipment for the general contractor to provide?
 - A: Per the Contract Specifications, the General Contractor (Keller) has hardware for the electronic security doors in his SOW. This includes Electric Hinges, Harnesses, Electric Latch Retraction Exit Devices, and Power Supplies. In the case of Door 103, the hardware also includes automatic door operator switches. Only the Card Reader is furnished and installed by the Security Contractor. Card Readers are to be provided for Doors 103 (noted in HW Set 8), Doors 130, and Door 141.
- 4. Q: Should we plan on tying in to the existing mechanisms on 103 and 130, and providing our own electrified locking strike on 141?
 - A: No. All door hardware shall be provided from one source through the General Contractor (Keller). Electric hardware will have to be added to the General contractor's SOW. Electrical tie-in shall be provided to the specified hardware.
- 5. Q:The maglock listed for Door 103, does it interface with the fire system to release in order to meet life safety requirements?
 - A: Yes the maglock will interface with the FA system in a FAIL SECURE mode.

6.	6. Q: Are we responsible for anything in regards to the Intrusion Detection System?	
	A: No	
	OTHER TERMS, CONDITIONS, AND SPECIFICATIONS opy of this signed addendum must accompany your res	
NAME	ME AND ADDRESS OF FIRM:	
		
		
		
PHONE	ONE #: EMAIL:	
NAME	ME OF AUTHORIZED REPRESENTATIVE:	
	Please Print	
SIGNA'	NATURE: DATE:	