

Topaz Road
Bid Number 1617-Eng 5
ADDENDUM 1

Whenever there is a conflict between this addendum and the initial proposal or plans, the addendum shall take precedence.

The following information is provided for clarification or changes as indicated:

A revised Form of Proposal is attached, adding the following Pay Items:

Clearing and Grubbing - remove all trees and brush to 25 feet each side of centerline or to the fences (except for fence to be relocated and replaced). Where ditches are not being moved or graded, large trees shall be flush cut to the ground and the root balls left in place to prevent erosion. In low areas where the adjacent area is below the road, the shoulders shall not be disturbed except to trim the trees and brush.

Fence

1. The wood lattice fence at approximately stations 33+30 to 35+40 must be relocated or replaced.
2. The fence on the west side at approximate stations 37+40 to 38+60 approximately 110 feet must be removed and replaced, including the posts on the north side of the driveway.

Concrete Ditch Paving 4"

At approximate station 56+10 north of the pipe add ditch paving approximately 20' long x 16' wide to redirect the water around the headwall.

Attached are revised drawings C-6 thru C-9.

C-9 Pipe at Station 59+76 has been changed to correct direction this is a double pipe also.

C-6 Thru C-9 text has been changed for clarity and easier reading.

Bidder must acknowledge receipt of all addenda as indicated on the bid form. Failure to acknowledge receipt of addenda may invalidate the bid. Both the bid form and the Pricing Sheets must be submitted with the bid.

Attachments: Bid Proposal; Drawings C-6 thru C-9