

UNIT PRICE WORK – SEWER SYSTEM IMPROVEMENTS					
ITEM NO.	DESCRIPTION	UNIT	EST. QTY	BID UNIT PRICE	BID PRICE
1501-2	GRINDER STATION, SANITARY SEWER, REMOBILIZATION POST FINAL COMPLETION	EA	59		
1501-3	SEPTIC TANK ABANDONMENT	EA	125		
0570-1-2	PERFORMANCE TURF (SOD)	SY	18883		
SUB-TOTAL OF ALL UNIT PRICE BID ITEMS (SEWER)				\$	
PAY ITEM NOTE:	0639-1-129	INCLUDES COST TO FURNISH AND INSTALL BREAKER AS NEEDED			
	0639-1-130	INCLUDES COST TO REPLACE EXISTING METER BASE WITH NEW METER/BREAKER COMBINATION BASE AND BREAKERS AS NEEDED			
	0639-2-1	INCLUDES COST OF ELECTRIC WIRE FROM RESIDENTIAL POWER SUPPLY TO CONTROL PANEL, CONDUIT AND FUSIBLE DISCONNECT AS NEEDED			
	1050-102-XXXX	INCLUDES COST OF CARRIER PIPE AND CONDUIT OR CASING AS REQUIRED BY CONSTRUCTION METHOD SPECIFICATION, MANUFACTURER RECOMMENDATIONS AND LOCAL CODE			
	1060-15-213	INCLUDES COST TO CONSTRUCT BOTH 4" AND 6" EXTERIOR FORCE MAIN DROP CONNECTIONS TO EXISTING MANHOLE.			
	1080-24-XXX	INCLUDES COST TO FURNISH AND INSTALL ASSOCIATED VALVE BOX			
	1080-21-100	INCLUDES COST TO FURNISH AND INSTALL ASSOCIATED SERVICE TAPPING SADDLE, CORPORATION STOP AND CURB STOP			
	1080-24-XXX	INCLUDES COST TO FURNISH AND INSTALL ASSOCIATED VALVE BOX			
	1501-1	TO BE FURNISHED WITH BARNES MODEL NO. OGP2022AUF SUBMERSIBLE GRINDER PUMP			
NOTE: * PAID ONLY IN THE EVENT OF ROCK REMOVAL, QUANTITIES INDICATE 3% OF COMBINED LENGTH OF PVC AND HDPE PIPES FOR THE RESPECTIVE SIZES					

UNIT PRICE WORK – WATER SYSTEM IMPROVEMENTS					
ITEM NO.	DESCRIPTION	UNIT	EST. QTY	BID UNIT PRICE	BID PRICE
3-0.1	WATER MOBILIZATION	LS	1		
3-0.2	WATER STAKEOUT	LS	1		
3-0.3	WATER BONDS & INSURANCE	LS	1		
3-0.4	BACTERIOLOGICAL & PRESSURE TESTING (PASSING)	LS	1		
1050-31-203	UTILITY PIPE- PVC, F&I, 3"	LF	557		
1050-31-206	UTILITY PIPE- PVC, F&I, 6"	LF	8369		
1050-31-208	UTILITY PIPE- PVC, F&I, 8"	LF	5682		
1050-31-210	UTILITY PIPE- PVC, F&I, 10"	LF	5949		
1050-41-201	UTILITY PIPE- PE, F&I, 1"	LF	33775		
1050-102-301	UTILITY PIPE- PE, TRENCHLESS, F&I, 1"	LF	2325		
1050-102-308	UTILITY PIPE- HDPE, TRENCHLESS, F&I, 8"	LF	790		