

ADDENDUM No.1
for
INVITATION FOR BID (IFB)

BLUEBERRY HILL ELEMENTARY SCHOOL LAWN
IRRIGATION

TOWN OF LONGMEADOW
MASSACHUSETTS

July 9, 2018

This document serves as Addendum No.1 for the Invitation for Bid (IFB) for Blueberry Hill Elementary School Lawn Irrigation. This Addendum forms part of the IFB and modifies the original document. Acknowledge the receipt of all addenda numbers issued on the BID SUBMISSION FORM. Failure to do so may subject the bidder to disqualification. The following changes and/or additions are to be made to the original Invitation for Bid document:

1. Change in bid deadline for the receipt of Bid Submission Forms:

Delete all reference to the bid deadline referenced in the original bid document of 11:00am on Friday, July 13, 2018. In its place insert the **revised bid deadline date and time for the receipt of Bid Submission Forms to Wednesday, July 18, 2018 at 11:00AM.**

2. Mandatory Pre-Bid Conference Attendance List:

Those that attended and registered during the mandatory pre-bid conference includes representation from the following organizations:

- Hydro-Pro, Chicopee, MA
- CMS Landscaping, Holyoke, MA
- Aqua-Turf Irrigation, Orange, CT
- Amherst Nurseries, Amherst, MA

If the Town accommodates a follow up site visit for only those that attended the mandatory pre-bid conference on June 28, 2018, then the follow up site visit(s) will not be mandatory.

3. Installation of a water source from inside of the school to just outside of the building for the irrigation system to connect to:

- Add water source from hallway through classroom, down the wall and then core through the brick.
- Tie into copper in the hallway.
- Piping insulated is required, 1" Thick, Hinged with Self Sealing Lap Fiberglass Pipe Insulation.
- Add shutoff – To be added in the hallway after tap onto 2-inch pipe.
- Backflow preventer-To be in the classroom ceiling before the pipe goes into the wall.

4. Electrical improvements required within the school associated with lawn irrigation system installation:

- The installation of a Town owned meter by the Contractor was mentioned during the mandatory pre-bid conference. The Town has now determined that a meter no longer needs to be supplied or installed by the Contractor.

- No power packs will be allowed.
- Tie the electrical connection into the same hallway as the water line. Its approximately the same distance as the water line.
- Contractor to return walls that require demo for construction work to pre-existing condition at project closeout. All interior sides of walls are drywall. The exterior wall is brick. The Contractor will supply all materials for returning walls back to pre-existing condition after construction installation. The Town will only supply the matching color paint for the Contractor to utilize for matching surrounding paint.

(End – Addendum No.1)