



Date: 7/30/18

Pre-Bid Amendment to the Construction Documents

Addendum #: 1

Project Name: Highland Horizons Pool Addition – **Brushy Creek Municipal Utilities District**,
Austin, TX

The following addenda was generated from questions and comments on July 26th at the
Non-Mandatory Pre-Bid Site Visit.

I. Drawings:

- A. Sheet A-1 – **Add** note to concrete flatwork – “UN-TINTED CONCRETE W/ SALT FINISH TO MATCH EXISTING TEXTURE”
- B. Sheet A-1 – **Revise** note to tree from “REKICATED TREE” to “NEW 5” CALIPER BURR OAK”. Contractor will be responsible for demolition and removal of existing tree.
- C. Sheet A-1 – **Add** note to new construction area stating “RELOCATE SPRINKLER CONTROLS WHERE SHOWN, OR ON BACK WALL – CONTRACTOR’S OPTION”
- D. Sheet A-2 – **Delete** note on Section 1 calling for ‘R-Panel’ – Roof to be standing seam to match existing.
- E. Sheet N-1 – **Add** General Note 1.8.D – “CONTRACTOR IS RESPONSIBLE FOR REPAIR ANY DAMAGED VEGETATION OUTSIDE LIMITS OF CONSTRUCTION – ALL DAMAGED GRASS TO BE RE-SODDED WITH LIKE & ANY BROKEN SPRINKLER HEADS OR LINES SHALL BE REPAIRED IN PLACE”
- F. Sheet N-1 – **Add Project Specification** note Select Demolition-Execution “4. CONTRACTOR SHALL REMOVE EXISTING SPRINKLER SYSTEM IN AREA OF CONSTRUCTION & RE-INSTALL HEADS OR CAP WHERE APPLICABLE”