



Public Utilities
 230 Hospital Road
 P.O. Box 761
 Smithfield, NC 27577
 919-934-2798 919-934-1688 (fax)

FORMAL REQUEST FOR QUOTE
(THIS IS NOT AN ORDER)

SEALED QUOTES will be received by the Town of Smithfield until **10:00 a.m., Friday, May 24, 2019**, at which time they will be publicly opened and read for the purchase of materials for the Booker Dairy Road North Feeder New Addition.

Please quote your best price, delivery (Smithfield, NC.) Items are subject to separate award. Alternate quotes may be considered on products that are equal to or better than the specified product, **except for the cable. ONLY OKONITE cable will be accepted.**

To receive consideration, **sealed quotes MUST BE mailed or hand delivered** to Smithfield Public Utilities Dept., P.O. Box 761, 230 Hospital Rd., Smithfield, NC by **10:00 a.m., Friday, May 24, 2019.** **Quotes received after this date will not be considered.** The Town of Smithfield reserves the right to reject any or all quotes.

For technical questions, please contact: Rodney Johnson 919-934-2230.

Item #	Item/Description	Qty.	Unit Price	Total	Lead Time
1	750 AL URD 25kV Cable – *Conductor footage include 3.5% additional length to allow for pulling, splices and scrap. OKONITE ONLY, NO SUB for following reels:				
	Reel 1 – Sub to Manhole 4	2375'			
	Reel 2 – Sub to Manhole 4	2375'			
	Reel 3 – Sub to Manhole 4	2375'			
	Reel 4 – Manhole 4 to Manhole 6	1740'			
	Reel 5 – Manhole 4 to Manhole 6	1740'			

	Reel 6 – Manhole 4 to Manhole 6	1740'			
	Reel 7 – Manhole 6 to JC 1 and JC 1 to JC 2	1435'			
	Reel 8 – Manhole 6 to JC 1 and JC 1 to JC 2	1435'			
	Reel 9 – Manhole 6 to JC 1 and JC 1 to JC 2	1435'			
2	UM6-3 Dead Break Termination – Elastimold or equal - K600, K650 series	12			
3	UM6-10 Insulated Protective Cap – Elastimold or equal – 273DRG3 200kV	6			
4	UM6-22 (600A) Four Point Junction – Elastimold or equal – J4-6226-25	6			
5	UM6-24 Outdoor Termination – Elastimold or equal – 16THGS	3			
6	UM6-28 In Line Primary Splice – 3M or equal – 5426-CI-750	6			
7	UM6-34 Dead Break Elbow Surge Arrestor – Elastimold or equal – 273ESA-18	6			
8	Arrestor, Lightning – Maclean or equal – ZHP018	9			
9	Mounting Bracket – Hubbell or equal – T2030289	9			
10	Connector, H-TAP – Penn-Union or equal – KO-R08	90			
11	Insulated Cable Support – Hubbell or equal – DU27M4	3			
12	Hook, Cable Rack – 18” – Hubbell or equal	7			
13	Cable Rack – 24” – Hubbell or equal	7			

ADDER 1

Item #	Item/Description	Qty.	Unit Price	Total	Lead Time
14	750 AL URD 25kV Cable – *Conductor footage include 3.5% additional length to allow for pulling, splices and scrap. OKONITE ONLY, NO SUB for following reels:				
	Reel 1 – Sub to Manhole 4	2375'			
	Reel 2 – Sub to Manhole 4	2375'			
	Reel 3 – Sub to Manhole 4	2375'			
	Reel 4 – Manhole 4 to Manhole 6	1740'			
	Reel 5 – Manhole 4 to Manhole 6	1740'			
	Reel 6 – Manhole 4 to Manhole 6	1740'			
	Reel 7 – Manhole 6 to Riser Pole (spliced at MH 7, 8, and 9)	2100'			
	Reel 8 – Manhole 6 to Riser Pole (spliced at MH 7, 8, and 9)	2100'			
	Reel 9 – Manhole 6 to Riser Pole (spliced at MH 7, 8, and 9)	2100'			
15	UM6-24 Outdoor Termination – Elastimold or equal – 16THGS	3			
16	UM6-28 In Line Primary Splice – 3M or equal – 5426-CI-750	18			
17	Arrestor, Lightning – Maclean or equal – ZHP018	3			
18	Mounting Bracket – Hubbell or equal – T2030289	3			
19	Insulated Cable Support – Hubbell or equal – DU27M4	3			
20	Hook, Cable Rack – 18” – Hubbell or equal	9			
21	Cable Rack – 24” – Hubbell or equal	2			

COMPANY NAME:
Date:
Bid Submitted By:
Street Address:
City/State/Zip:
Phone #:
Fax #:
Email:
Quote Valid for _____ days
Delivery Guaranteed _____ calendar days after receipt of order