



JACKSON COUNTY ROAD & BRIDGE

Phone (850) 482-9633
Fax (850) 482-9643
www.jacksoncountyfl.net

2828 Owens St
Marianna, Florida 32446

District's 1 Chip Seal & Asphalt Paving Project Addendum #3

To: Bidders

From: Scotty Taylor, Public Transportation Director
Jackson County Board of County Commissioners

Email: taylor@jacksoncountyfl.gov

Date: 9/22/2020

Regarding: Addendum # 3

MESSAGE:

Addendum #3 involves the following changes, adjustments, and/or clarifications:

Changes/Adjustments:

1. Correct the error on the Asphalt Pavement Option Bid Proposal. Clearmont Rd had a line item for Double Chip Seal that was incorrectly entered. This line item has been deleted and the Bid Proposal pages have been re-issued for the Chip Seal and Asphalt Pavement Option. The 8 pages included with this addendum will replace the original 8 pages in the bid documents.
2. Testing requirements for the subgrade and base materials is accordance with current FDOT standards. Asphalt pavement testing requirements will be in accordance with FDOT – Density by Nuclear Density Gauge and cores will only be taken if the asphalt thickness is in question.
3. Be advised that each contractor can price either the Chip Seal Option or the Asphalt Pavement Option. Both options can be priced but isn't required.

Sincerely,

Scotty Taylor
Public Transportation Director

District 1 Chip Seal and Asphalt Paving Project
CHIP SEAL OPTION BID PROPOSAL

Clearmont Rd Chip Seal Bid Proposal					
From End of Pavement 3586 LF - 18' Wide to Beginning of Pavement at Skyview Dr					
Item	DESCRIPTION	UNIT	UNIT PRICE	QUANTITY	TOTAL
1	Mobilization	EA		1	
2	Maint of Traffic	EA		1	
3	Grade and Compact Subgrade	SY		7172	
4	4" Limerock Base	TN		1555	
5	Prime and Sand Base	SY		7172	
6	Double Chip Seal	SY		7172	
7	Double Chip Seal Driveways and Side Roads	EA		6	
8	Fog Seal	SY		7172	
9	Sodding Bahia	SY		1200	
				Total Bid	

Bellamy Bridge Rd Chip Seal Overlay Proposal					
Entire Road - 10243 LF with 18' Wide Roadway					
Item	DESCRIPTION	UNIT	UNIT PRICE	QUANTITY	TOTAL
1	Mobilization	EA		1	
2	Maint of Traffic	EA		1	
3	Clean and Sweep Roadway	SY		20486	
4	Double Chip Seal	SY		20486	
5	Double Chip Seal Driveways and Side Roads	EA		18	
6	Fog Seal	SY		20846	
7	Double Micro Surface Leveling	SY		1000	
				Total Bid	

Bump Nose Road Chip Seal Bid Proposal					
Unpaved Portion - 18850 LF - 20' Wide					
ITEM	DESCRIPTION	UNIT	UNIT PRICE	QUANTITY	TOTAL
1	Mobilization	EA		1	
2	Maint of Traffic	EA		1	
3	Grade and Compact Subgrade	SY		46317	
4	Regular Excavation	CY		4000	
5	6" Limerock Base	TN		10035	
6	Prime and Sand Base	SY		46317	
7	Grade Shoulders and Ditches	SY		18500	
8	Double Chip Seal	SY		46317	
9	Double Chip Seal Driveways and Side Roads	EA		14	
10	Hydroseeding	SY		15000	
11	Sodding Bahia	SY		6000	
				Total Bid	

Valley Oaks Drive Chip Seal Proposal					
Entire Road - 3020 LF with 18' Wide Roadway					
ITEM	DESCRIPTION	UNIT	UNIT PRICE	QUANTITY	TOTAL
1	Mobilization	EA		1	
2	Maint of Traffic	EA		1	
3	Clean and Sweep Roadway	SY		6040	
4	Double Micro Surface Leveling	SY		200	
5	Double Chip Seal	SY		6040	
6	Double Chip Seal Driveways and Side Roads	EA		16	
7	Sodding Bahia	SY		1000	
				Total Bid	

London Rd Chip Seal Bid Proposal					
Entire Road - 5068 LF with 20' Wide Roadway					
Item	DESCRIPTION	UNIT	UNIT PRICE	QUANTITY	TOTAL
1	Mobilization	EA		1	
2	Maint of Traffic	EA		1	
3	Grade and Compact Subgrade	SY		11263	
4	4" Limerock Base	TN		2500	
5	Prime and Sand Base	SY		11263	
6	Double Chip Seal	SY		11263	
7	Double Chip Seal Driveways and Side Roads	EA		18	
8	Fog Seal	SY		11263	
9	Sodding Bahia	SY		1690	
				Total Bid	

Russ Road Chip Seal Bid Proposal					
Beginning at Intersection of Limestone Ln going South to Dead End -					
ITEM	DESCRIPTION	UNIT	UNIT PRICE	QUANTITY	TOTAL
1	Mobilization	EA		1	
2	Maint of Traffic	EA		1	
3	Base Material - Asphalt Milling	TN		300	
4	Double Chip Seal	SY		3100	
5	Double Chip Seal Driveways and Side Roads	EA		11	
6	Fog Seal	SY		3100	
7	Double Micro Surface Leveling(if needed)	SY		1000	
8	Sodding Bahia	SY		500	
				Total Bid	

Lovewood Road Chip Seal Bid Proposal					
From Peanut Rd(CR 169) 5003 LF - 20' Wide SR 231					
ITEM	DESCRIPTION	UNIT	UNIT PRICE	QUANTITY	TOTAL
1	Mobilization	EA		1	
2	Maint of Traffic	EA		1	
3	Grade and Compact Subgrade	SY		8024	
4	Regular Excavation	CY		800	
5	Bump	TN		1920	
6	Russ	SY		4000	
7	Prime and Sand Base	SY		8024	
8	Double Chip Seal	SY		8024	
9	Double Chip Seal Driveways and Side Roads	EA		12	
10	Sodding Bahia	SY		1668	
				Total Bid	

Bidder acknowledges that each Bid Unit Price includes an amount considered by Bidder to be adequate to cover Contractor's overhead and profit for each separately identified item, and quantities are estimated. Each item will be paid as units in place as measure in field or by tickets provided at time of placement.

Bidder acknowledges that the County reserves the right to award all roadways, but that there is no guarantee that the County will award all roadways. The number of roadways that will be awarded will be based on available funding at the time of bid award. The bid award is anticipated to be on or before October 31, 2020.

District 1 Chip Seal and Asphalt Paving Project

ASPHALT PAVEMENT OPTION BID PROPOSAL

Clearmont Rd Asphalt Pavement Bid Proposal					
From End of Pavement 3586 LF - 18' Wide to Beginning of Pavement at Skyview Dr					
ITEM	DESCRIPTION	UNIT	UNIT PRICE	QUANTITY	TOTAL
1	Mobilization	EA		1	
2	Maint of Traffic	EA		1	
3	Grade and Compact Subgrade	SY		7172	
4	4" Limerock Base	TN		1555	
5	1.5" Type SP 9.5 Asphalt	TN		592	
6	Turnout Construction - Driveways and Side Roads	SY		180	
7	Sodding Bahia	SY		1200	
				Total Bid	

London Rd Asphalt Pavement Bid Proposal					
Entire Road - 5068 LF with 20' Wide Roadway					
ITEM	DESCRIPTION	UNIT	UNIT PRICE	QUANTITY	TOTAL
1	Mobilization	EA		1	
2	Maint of Traffic	EA		1	
3	Grade and Compact Subgrade	SY		11263	
4	4" Limerock Base	TN		2500	
5	1.5" Type SP 9.5 Asphalt	TN		945	
6	Turnout Construction - Driveways and Side Roads	SY		365	
7	Sodding Bahia	SY		1690	
				Total Bid	

Russ Road Asphalt Pavement Bid Proposal					
Beginning at Intersection of Limestone Ln going South to Dead End -					
ITEM	DESCRIPTION	UNIT	UNIT PRICE	QUANTITY	TOTAL
1	Mobilization	EA		1	
2	Maint of Traffic	EA		1	
3	Base Material - Asphalt Milling	TN		300	
4	1.5" Type SP 9.5 Asphalt	TN		256	
5	Turnout Construction - Driveways and Side Roads	SY		225	
6	Sodding Bahia	SY		500	
				Total Bid	

Bellamy Bridge Rd Asphalt Pavement Bid Proposal					
Entire Road - 10243 LF with 18' Wide Roadway					
Item	DESCRIPTION	UNIT	UNIT PRICE	QUANTITY	TOTAL
1	Mobilization	EA		1	
2	Maint of Traffic	EA		1	
3	Clean and Sweep Roadway	SY		20486	
4	65 lb/sy Asphalt for Leveling as needed	TN		350	
5	Tack Coat	SY		20486	
6	1" Type SP 9.5 Asphalt	TN		1130	
7	Asphalt Driveway Connection (avg 6' from edge of road)	EA		18	
8	Turnout Construction (Intersection of Essex Rd)	SY		70	
				Total Bid	

Bump Nose Road Asphalt Pavement Bid Proposal					
Unpaved Portion - 18850 LF - 20' Wide					
ITEM	DESCRIPTION	UNIT	UNIT PRICE	QUANTITY	TOTAL
1	Mobilization	EA		1	
2	Maint of Traffic	EA		1	
3	Grade and Compact Subgrade	SY		46317	
4	Regular Excavation	CY		4000	
5	6" Limerock Base	TN		10035	
6	Grade Shoulders and Ditches	SY		18500	
7	2" Type SP 9.5 Asphalt	TN		3975	
8	Asphalt Driveway Connection(avg 6' from edge of road)	SY		200	
9	Turnout Construction-Side Road Connections	SY		360	
10	Hydroseeding	SY		15000	
11	Sodding Bahia	SY		6000	
				Total Bid	

Valley Oaks Drive Asphalt Overlay Proposal					
Entire Road - 3020 LF with 18' Wide Roadway					
ITEM	DESCRIPTION	UNIT	UNIT PRICE	QUANTITY	TOTAL
1	Mobilization	EA		1	
2	Maint of Traffic	EA		1	
3	Clean and Sweep Roadway	SY		6040	
4	65 lb/sy Asphalt for Leveling	TN		150	
5	Tack Coat	SY		6040	
6	1" Type SP 9.5 Asphalt	TN		350	
7	Asphalt Driveway Connection(avg 6' from edge of road)	EA		16	
8	Sodding Bahia	SY		1000	
				Total Bid	

Lovewood Road Asphalt Pavement Bid Proposal					
From Peanut Rd(CR 169) 5003 LF - 20' Wide SR 231					
ITEM	DESCRIPTION	UNIT	UNIT PRICE	QUANTITY	TOTAL
1	Mobilization	EA		1	
2	Maint of Traffic	EA		1	
3	Grade and Compact Subgrade	SY		8024	
4	Regular Excavation	CY		800	
5	4" Limerock Base	TN		1920	
6	Grade Shoulders and Ditches	SY		4000	
7	65 lb/sy Asphalt for Leveling	TN			
8	2" Type SP 9.5 Asphalt	TN		1235	
9	1" Type SP 9.5 Asphalt(Overlay existing paved areas)	TN		151	
10	Tack	SY		3188	
11	Asphalt Driveway Connection(avg 6' from edge of road)	EA		12	
12	Sodding Bahia	SY		1668	
				Total Bid	

Bidder acknowledges that each Bid Unit Price includes an amount considered by Bidder to be adequate to cover Contractor's overhead and profit for each separately identified item, and quantities are estimated. Each item will be paid as units in place as measure in field or by tickets provided at time of placement.

Bidder acknowledges that the County reserves the right to award all roadways, but that there is no guarantee that the County will award all roadways. The number of roadways that will be awarded will be based on available funding at the time of bid award. The bid award is anticipated to be on or before October 31, 2020.