



JACKSON COUNTY ROAD & BRIDGE

Phone (850) 482-9633
Fax (850) 482-9643
www.jacksoncountyfl.net

2828 Owens St
Marianna, Florida 32446

District 2 Chip Seal with Asphalt Paving Option 4177 Project Addendum #1

To: Bidders

From: Scotty Taylor, Public Transportation Director
Jackson County Board of County Commissioners

Email: taylor@jacksoncountyfl.gov

Date: 11/23/2020

Regarding: Addendum # 1

MESSAGE:

Addendum #1 involves the following changes, adjustments, and/or clarifications:

Changes/Adjustments:

1. Change limerock thickness on both options to a 4" thickness. Added 4" limerock base to driveways on the Chip Seal Option. Change the Open Graded Asphalt to 1" layer of Type SP 9.5 Asphalt for the roadway and driveway on the Asphalt Bid Option. Bid Proposals have been updated and attached to this letter and an excel file has been provided for your use.

Sincerely,

Scotty Taylor
Public Transportation Director

District 2 Chip Seal & Asphalt Paving 4177 Project
Jackson County Board of County Commissioners
BID # 2021-ENG-001

Shiloh Church Road (from Shiloh Church Loop to SR 2) (Length 6090 LF & Width 20 FT)					
ITEM	DESCRIPTION	UNIT	UNIT PRICE	QUANTITY	TOTAL
1	Mobilization	LS		1	
2	Maintenance of Traffic (MOT)	LS		1	
3	Shape, Grade and Stabilize	SY		20,300	
4	Haul and Place Fill Material	CY		300	
5	4" Limerock Base	TN		1,936	
6	Prime	SY		13,780	
7	Double Chip Seal #57 or #67 with #89 Granite	SY		13,533	
8	Double Chip Seal Driveways & Side Roads with 4" Limerock Base	SY		259	
9	Fog Seal	SY		13,780	
10	Sod (Bahia or match existing)	SY		6,767	
11	Hydroseed	SY		8,120	
12	Painted Pvmt Markings, 24" Stop Bar	EA		6	
13	Painted Pvmt Mark, Std. Solid Yellow 6"	NM		1.25	
14	Thermoplastic, Std, White 24" Stop Bar	EA		6	
15	Thermoplastic, Std, Yellow, Solid 6"	NM		1.25	
				Total Bid	

Syfrett Road (Length 10786 LF & Width 20 FT)					
ITEM	DESCRIPTION	UNIT	UNIT PRICE	QUANTITY	TOTAL
1	Mobilization	LS		1	
2	Maintenance of Traffic (MOT)	LS		1	
3	Shape, Grade and Stabilize	SY		35,953	
4	Haul and Place Fill Material	CY		300	
5	4" Limerock Base	TN		3,456	
6	Prime	SY		24,636	
7	Double Chip Seal #57 or #67 with #89 Granite	SY		23,969	
8	Double Chip Seal Driveways & Side Roads with 4" Limerock Base	SY		667	
9	Fog Seal	SY		24,636	
10	Sod (Bahia or match existing)	SY		11,984	
11	Hydroseed	SY		14,381	
12	Painted Pvmt Markings, 24" Stop Bar	EA		5	
13	Painted Pvmt Mark, Std. Solid Yellow 6"	NM		2.14	
14	Thermoplastic, Std, White 24" Stop Bar	EA		5	
15	Thermoplastic, Std, Yellow, Solid 6"	NM		2.14	
				Total Bid	

Collins Road (7865 LF & Width 18FT)					
ITEM	DESCRIPTION	UNIT	UNIT PRICE	QUANTITY	TOTAL
1	Mobilization	LS		1	
2	Maintenance of Traffic (MOT)	LS		1	
3	Shape, Grade and Stabilize	SY		24,469	
4	Haul and Place Fill Material	CY		600	
5	4" Limerock Base	TN		2,393	
6	Prime	SY		16,530	
7	Double Chip Seal #57 or #67 with #89 Granite	SY		15,730	
8	Double Chip Seal Driveways & Side Roads with 4" Limerock Base	SY		800	
9	Fog Seal	SY		16,530	
10	Sod (Bahia or match existing)	SY		8,739	
11	Hydroseed	SY		10,487	
12	Painted Pvmt Markings, 24" Stop Bar	EA		8	
13	Painted Pvmt Mark, Std. Solid Yellow 6"	NM		1.51	
14	Thermoplastic, Std, White 24" Stop Bar	EA		8	
15	Thermoplastic, Std, Yellow, Solid 6"	NM		1.51	
				Total Bid	

Chip Seal Bid Summary by Road	
Road Name	Total Bid Price of Road
Shiloh Church Rd	
Syfrett Rd	
Collins Rd	
TOTAL BID PRICE(SUM OF LISTED ROADS)	

Total Amount of the Base Bid(Basis of Award)(Total Cost of all of Listed Roads from Above)

\$ _____
(Amount in Figures)

(Amount in Words)

NOTES:

-All work will be paid as completed units in place.

-Bidder acknowledges that (1) each Bid Unit Price includes an amount considered by bidder to be adequate to cover Contractor's overhead and profit for each separately identified item, and (2) estimated quantities are not guaranteed, and are solely for the purpose of comparison of Bids, and final payment for all unit price Bid Items will be based on actual quantities, determined as provided in the Contract Documents.

-Jackson County reserves the right to delete some of the roads listed above or add additional roads base on the available funding.

District 2 Chip Seal with Asphalt Paving Option 4177 Project
Jackson County Board of County Commissioners
Asphalt Bid Option
BID # 2021-ENG-001

Shiloh Church Road (from Shiloh Church Loop to SR 2) (Length 6090 LF & Width 20 FT)					
ITEM	DESCRIPTION	UNIT	UNIT PRICE	QUANTITY	TOTAL
1	Mobilization	LS		1	
2	Maintenance of Traffic (MOT)	LS		1	
3	Shape, Grade and Stabilize	SY		20,300	
4	Haul and Place Fill Material(If Needed)	CY		300	
5	4" Limerock Roadway	TN		1,936	
6	1" Asphalt SP 9.5	TN		810	
7	4" Limerock Driveways	TN		60	
8	1" S-3 or SP 9.5 Asphalt - Driveways	TN		22	
9	Sod (Bahia or match existing)	SY		6,767	
10	Hydroseed	SY		8,120	
11	Painted Pvmt Markings, 24" Stop Bar	EA		6	
12	Painted Pvmt Mark, Std. Solid Yellow 6"	NM		1.25	
13	Thermoplastic, Std, White 24" Stop Bar	EA		6	
14	Thermoplastic, Std, Yellow, Solid 6"	NM		1.25	
				Total Bid	

Syfrett Road (Length 10786 LF & Width 20 FT)					
ITEM	DESCRIPTION	UNIT	UNIT PRICE	QUANTITY	TOTAL
1	Mobilization	LS		1	
2	Maintenance of Traffic (MOT)	LS		1	
3	Shape, Grade and Stabilize	SY		35,953	
4	Haul and Place Fill Material(If Needed)	CY		300	
5	4" Limerock Roadway	TN		3,456	
6	1" Asphalt SP 9.5	TN		1,330	
7	4" Limerock Driveways	TN		130	
8	1" S-3 or SP 9.5 Asphalt - Driveways	TN		55	
9	Sod (Bahia or match existing)	SY		11,984	
10	Hydroseed	SY		14,381	
11	Painted Pvmt Markings, 24" Stop Bar	EA		5	
12	Painted Pvmt Mark, Std. Solid Yellow 6"	NM		2.14	
13	Thermoplastic, Std, White 24" Stop Bar	EA		5	
14	Thermoplastic, Std, Yellow, Solid 6"	NM		2.14	
				Total Bid	

Collins Road (7865 LF & Width 18FT)					
ITEM	DESCRIPTION	UNIT	UNIT PRICE	QUANTITY	TOTAL
1	Mobilization	LS		1	
2	Maintenance of Traffic (MOT)	LS		1	
3	Shape, Grade and Stabilize	SY		24,469	
4	Haul and Place Fill Material(If Needed)	CY		600	
5	4" Limerock Roadway	TN		2,393	
6	1" Asphalt SP 9.5	TN		925	
7	4" Limerock Driveways	TN		100	
8	1.5 S-3 or SP 9.5 Asphalt - Driveways	TN		40	
9	Sod (Bahia or match existing)	SY		8,739	
10	Hydroseed	SY		10,487	
11	Painted Pvmt Markings, 24" Stop Bar	EA		8	
12	Painted Pvmt Mark, Std. Solid Yellow 6"	NM		1.51	
13	Thermoplastic, Std, White 24" Stop Bar	EA		8	
14	Thermoplastic, Std, Yellow, Solid 6"	NM		1.51	
				Total Bid	

Asphalt Option Bid Summary by Road	
Road Name	Total Bid Price of Road
Shiloh Church Rd	
Syfrett Rd	
Collins Rd	
TOTAL BID PRICE(SUM OF LISTED ROADS)	

Total Amount of the Base Bid(Basis of Award)(Total Cost of all of Listed Roads from Above)

\$ _____
(Amount in Figures)

(Amount in Words)

NOTES:

- All work will be paid as completed units in place.
- Bidder acknowledges that (1) each Bid Unit Price includes an amount considered by bidder to be adequate to cover
- Jackson County reserves the right to delete some of the roads listed above or add additional roads base on the available funding.